



NOTES:

1 - GROUNDING CONDUCTOR SHALL BE ATTACHED TO GROUND LUG INSIDE METER BASE.

Item No.	Material	Qty.	Item No.	Material	Qty.
1	1Ø. 200A METER BASE	1	8	2" SCH. 80 36"R PVC SWEEP	1
2	WEATHERPROOF BREAKER BOX	1	9	6"x 6"x8' TREATED WOOD POST	1
3	2-1/2", SCH. 80 PVC CONDUIT	As Req'd.	10	2"x 6" TREATED WOOD PLANK	As Req'd.
4	2" SCH. 80 PVC CONDUIT	As Req'd.	11	GROUND ROD, 5/8"x 8' COPPERWELD	1
5	2-1/2" CONDUIT CLAMP	2	12	CONDUCTOR, #4 BARE COPPER	As Req'd.
6	2" CONDUIT CLAMP	2			
7	2-1/2" SCH. 80 36"R PVC SWEEP	1			

BY: CKD

DATE: 11/15/03



1Ø MOBILE HOME
PERMANENT UNDERGROUND
METER ASSEMBLY (TYPE II)

STANDARD
DETAIL

SK-80